

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

13-147-20283-00-00

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -147-20,283 (of this well)

Operator's Full Name ARROWHEAD PETROLEUM INC.

Complete Address BOX 8287 - MUNGER STATION - WICHITA, Mo. 67208

Lease Name MILLER Well No. #1

Location NE-NW-NW Sec 34 Twp. 3 Rge. 18 (E) (W) W

County PHILLIPS Total Depth 3575 EX

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor BIG SPRINGS DRILLING

Address BOX 8287 MUNGER STATION - WICHITA License No. _____

Operation Completed: Hour 10:00 ^{AM} Day 15 TH Month AUG. Year 1980

The Above well was plugged as follows:

8 7/8" 251' SP. CUL. w/ 175' COMMON 2% GEL. - 2% CA-CL.

ORDERED 110' 50/50 PORMIX 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1' PLUG. @ 1050' w/ 70' CNT.

2' PLUG. @ 240' w/ 25' CNT.

3' PLUG. - SOLID BRIDGE HULL'S PLUG. @ 40' to 0' w/ 10' CNT.

5' IN PAT HOLE.

CEMENTED BY SUN CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature]
Well Plugging Supervisor

DATE 8-19-80

INV. NO. 2887-w

AUG 18 1980

CONSERVATION DIVISION
Wichita, Kansas

8-18-80