

KANSAS

AP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20050-00-00

10-28-68
RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beacon Resources Corporation

Complete Address: 312 Union Center Wichita, Kansas

Lease Name Zillinger "A" Well No. 1

Location NE SW SW Sec. 33 Twp. 3 Rge. 18 (E) (W) X

County Phillips Total Depth 3580

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons

Address: Victoria, Kansas License No.

Operation Completed: Hour 7P Day 26 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3580' 8 5/8 csg set at 252' cwc Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Dreiling
Well Plugging Supervisor

DATE 10/28/68

INV. NO. 8902-W