

15-147-00886-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CSE NE

SEC. 2 TWP. 3 RGE. 19 W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Eltiste Box 786

Operator Carter Oil Co Address Great Bend, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3310 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 270' circulated with cement - 5 1/2" at 3308' with 100  
sax behind, P.B. with cement to 3230', top perforations at  
3123'.

Filled with sand and rock to 3115', set 4 sax cement with dump  
bailer, pulled 1000' 5 1/2", filled hole with mud to 270', set rock  
bridge and 15 sax cement, filled hole with mud to 35', set  
rock and 10 sax cement to bottom cellar.

RECEIVED  
FILE SEC. 2 TWP. 3 RGE. 19 W COMMISSION  
BOOK PAGE 59 LINE 42 1951 2-3-51  
CONSERVATION DIVISION  
Wichita, Kansas

E. P. Perry  
District Conservation Agent

Date 1-31-51