

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1967

11-13-67

CONSERVATION DIVISION
WICHITA, KANSAS

15-147-00888-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Humble Oil & Refining Company

Complete Address: 2000 Classen Center-North Building Okla. City, Oklahoma

Lease Name August Eltiste Well No. 1

Location C NE NE Sec. 11 Twp. 3 Rge. 19 (E) (W) W

County Phillips Total Depth 3308

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Russ Casing Pulling

Address: _____ License No. _____

Operation Completed: Hour 5:30 P Day 8 Month 11 Year 1967

The Above well was plugged as follows:

Total Depth 3308' 8 5/8 csg set at 281' cwc 115 sc

5 1/2 csg set at 3304' cw 150 sc cement.

Top perf. 3118' Plug at 3000', Poured 25' sand and dumped 5 sc cem. with dump bailer.

Recov. 1219' of 5 1/2 csg.

Pumped down 8 5/8 csg with 125 sc 50-50 poz cement with 6% gel and 35 sc gel. mud.

Cement (0-250) gel (250-650) cement (650-950) and gel 950 to TD

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messer
Well Plugging Supervisor

DATE 11/13/67

INV. NO. 6661-W