

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00883-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 84-27  
LOCATION C SW SW  
SEC. 1 TWP. 3 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Klotz

Operator Tom Allen Address Wichita, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3221 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 53' - 7" at 3172' with 100 sax cement behind.  
Filled with chat to 3160', set 4 sax cement with dump  
bailer, pulled 1400' 7", filled hole with mud to 200',  
set rock and 20 sax cement, filled with mud to 35', set  
bridge and 10 sax cement to bottom cellar.

7-3-51

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 3 1951

CONSERVATION DIVISION  
Wichita, Kansas

*John J. [Signature]*  
District Conservation Agent

Date 6-25-51

**PLUGGING**  
FILE SEC 1 T 3 R 19  
BOOK PAGE 89 LINE 27