

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00065-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE NE NW

SEC. 10 TWP. 3 RGE. 19 W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1a Lease Preuss

Operator Lewis Dng Co Address Wichita, Kans

Field _____ County Phillips

Total Depth 3410 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 146' circulated with cement - 5 1/2" at 3410'

With 100 sax cement behind - top perforations at 3260'.

Filled with sand to 3250', set 4 sax cement with dump bailer,

pulled 2700' 5 1/2", filled hole with mud to 100', set rock to

100', and 10 sax cement, mud to 55', rock and 10 sax cement

to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN - 8 1952

CONSERVATION DIVISION

1-8-52

Edward Perry
District Conservation Agent

Date 1-5-52

F

PLUGGING

FILE SEC 10 T 3 R 19 W
BOOK PAGE 136 LINE 18