

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-147-20, 350-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address 7701 E. Kellogg, Suite 780, Box 18407, Wichita, KS

Lease Name Wells "A" Well No. 1

Location NW-5W Sec. 3 Twp. 3 Rge. 19 (East) (~~West~~)

County Phillips Total Depth 3635

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc.

Address 7701 E. Kellogg - Suite 780, Box 18407 - Wichita, KS License No. —

Operation Completed: Hour: 11:15 Day: 21 Month: Jan Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 327' S.P. circ. cmt. w/250 sk - 2% gel - 3% ca-d (Allied)
Ordered 130 sk. 5/8" pozmix 4% gel - 3% CA-d + 8 5/8" plug
1st-plug @ 960' w/70 sk. Cmt.
2nd-plug @ 300' w/40 sk. Cmt.
3rd - Solid bridge - Hulls + plug @ 40' to 0' 10 sk. Cmt.
Rat-hole - 10 sk cmt - Spot w/drill stem - Circ. heavy
mud between all plugs.

(Cmt. by Allied)

Amount of Surface Casing: 327'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Out on plugging job for Frontier Oil Co. - Posegate #1
+ Harrison.

INDEXED
2982
9378-W
INV. NO.

Signed: Dennis L. Hamel
Conservation Division Agent

STATE CORPORATION COMMISSION
1-27-82
CONSERVATION DIVISION