

DISTRICT CONSERVATION AGENT'S REPORT
15-147-00885-00-00

h

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-147-00885-00-00

LOCATION NW, NW

SEC. 1 TWP. 3 RGE. 19

Dry Hole - Abandoned Oil Well yes Abandoned Gas Well -

I have today completed supervision of plugging of:

Well No. 2 Lease Logie Gate

Operator WA Paglin Address 275 1st Blvd. Kan

Field - County Phillips

Total Depth 3355 Feet.


(Describe briefly the manner in which the well was plugged)

This hole was filled mud + bridged 3355 to 3150
cement 3150 ft to 3110 ft 5" x 5" mud 3110 to 250
ft cement 250 to 205. 15" x 5" mud 205 to 10 ft
 cement into face of well at 10 ft
289 ft of 5 7/8" pipe cemented + left in hole

A. W. K...
District Conservation Agent

Date July 24, 1946

1 ~~3~~ 19
71 2



9-19-46