

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-147-20,298-00-00

LEASE NAME EHM-Stuttgart

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

3630 Ft. from (S) Section Line

560 Ft. from (E) Section Line

SEC. 23 TWP. 35 RGE. 19 (W)

COUNTY Phillips

Date Well Completed 12-11-80

Plugging Commenced 5-12-2000

Plugging Completed 5-12-2000

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 14201 E Central Wichita Ks 67230

PHONE#(316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on MAY 13, 2000 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Filed w/ Plugging Application

Producing Formation LKC Depth to Top 3153 Bottom 3182 T.D. 3340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	211	8-5/8	211	0
<u>LKC</u>	<u>Oil/Water</u>	0	3339	4-1/2	3339	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
RAN tubing to 2000' Spot 60 SX + 300# hulls. Pull to 900' Circulate
To Surface w/ 80 SX + 200# hulls. Pull tubing. Pump 30 SX @ 400 PSI SHUT
IN w/ 300 PSI Pump 30 SX down ANNULUS @ 200 PSI MAX. STW/100 PSI.
All cement 60/40 Poz + 10% Gel

Name of Plugging Contractor Pfeifer Dozer Service License No. 32,579

Address HCR 01 Box 63 St. Peter, Ks 67650

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF KANSAS COUNTY OF Sedgwick, ss.

GARY L. Reed

Agent
 (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Gary L. Reed

(Address) 14200 Brookline Ct Wichita Ks 67230

RECEIVED

SUBSCRIBED AND SWORN TO before me this

19 day of May, 2000



MAY 22 2000

Dana R. Clothier
 Notary Public

11-13-2000