

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-147-20,179-00-00

LEASE NAME E.H.M. Stuhgart

WELL NUMBER 1

330 Ft. from S Section Line

760 Ft. from E Section Line

SEC. 23 TWP. 3 RGE. 19 (E or W)

COUNTY Phillips

Date Well Completed 11-5-74

Plugging Commenced 5-23-2000

Plugging Completed 5-23-2000

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Petroleum Management, Inc

ADDRESS 14201 E. Central Wichita, Ks 67230

PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-22-2000 (date)

by Herb Deines KCC DIST # 4 (KCC District Agent's Name).

Is ACO-1 filed? No ACO IN If not, is well log attached? Yes  
 1974

Producing Formation LKC Depth to Top 3172 Bottom 3236 T.D. 3343

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD RECEIVED STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
SURFACE	Water	0	213	8-5/8	263	0
LKC	Oil-Water			4-1/2	3341	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
RAW tubing to 2500'. Spot 100 sx Cement + 300# hulls. Pull to 1400'  
Circulate to Surface w/ 120 sx + 200# hulls. Pull tubing, pump 40 sx @ 500#  
MAX SI w/ 300#. Pump down Annulus w/ 50 sx + 100# hulls @ 300# MAX 100# SI  
All cement 60/40 Poz + 10% gel

Name of Plugging Contractor Pfeifer Dozer Service License No. 32579

Address HCR 01 Box 63 St. Peter, KS 67650

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF KANSAS COUNTY OF Sedgwick, ss.


GARY L. Reed Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Gary Reed


(Address) 14200 Brookline Ct, Wichita KS 67230

SUBSCRIBED AND SWORN TO before me this 1 day of June, 2000

Dana R. Clothier  
 Notary Public



Commission Expires: 11-13-2000



DRILLERS LOG

No. 1 Stuttgart-Ehm

CASING RECORD:	COMPANY	Petroleum Management, Inc.	DESCRIPTION:
8-5/8" @ 213' w/150 sx. cmt.	CONTRACTOR:	Red Tiger Drilling Co.	100' West of C S/2 SE NE
4-1/2" @ 3340.80' w/150 sx. cmt.	COMMENCED:	October 4, 1974	23-35-19W Phillips County, Kansas
TOTAL DEPTH: 3343	COMPLETED:	October 10, 1974	ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	215	
Post Rock & Shale	215	690	
Shale, Sand & Shale	690	1528	
Anhydrite	1528	1568	
Shale	1568	2060	
Shale & Lime	2060	2555	
Lime & Shale	2555	2730	
Lime	2730	2880	
Shale & Lime	2880	2985	
Lime	2985	3343	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY


*Linda H. Dickens*  
Linda H. Dickens

Subscribed and sworn to before me this 15th day of October, 1974.

*D. Ann Drennan*  
Notary Public

My Commission Expires:

December 28, 1977



# ALLIED CEMENTING CO., INC.

3603

Federal Tax I.D.# ~~48-7000~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

*Russell*

DATE <u>5-23-00</u>	SEC. <u>14</u>	TWP <u>3</u>	RANGE <u>19</u>	CALLED OUT	ON LOCATION <u>3:00pm</u>	JOB START	JOB FINISH <u>5:00pm</u>
LEASE <u>Stuttgart</u> WELL # <u>1</u>			LOCATION <u>Speed 65 W.N</u>		COUNTY <u>Phillips</u>	STATE <u>K</u>	
OLD OR NEW (Circle one)							

CONTRACTOR P. Pfeifer well service

OWNER

TYPE OF JOB plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 4 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 2 3/8 DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

**EQUIPMENT**

PUMP TRUCK CEMENTER Bill

# 153 HELPER P.H.C.

BULK TRUCK \_\_\_\_\_

# 259 DRIVER Dason

BULK TRUCK \_\_\_\_\_

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

*Tubing @ 2500 spot 100#  
w/ 300 # Halls pull to 1400  
Circ. cement w/ 120 # w/ 200 # Halls  
Pump down 4 1/2" casing w/ 40 #  
max 500 # 300 # shut in  
Pump down Annul seal w/  
100 # Halls max 300 # shut in 100 #*

**SERVICE**

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 195.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE @ \_\_\_\_\_

PLUG @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 195.00

CHARGE TO: P.M.F.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**FLOAT EQUIPMENT**

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Suzie Wallert

PRINTED NAME \_\_\_\_\_