


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-147-00672-00-00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Phillips County. Sec. 23 Twp. 3 Rge. XX 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4
Lease Owner Phillips Petroleum Company
Lease Name Hempler Well No. 4
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 20, 19 52
Application for plugging filed June 16, 19 52
Application for plugging approved June 18, 19 52
Plugging commenced June 20, 19 52
Plugging completed June 20, 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Lansing-Kansas city Depth to top 3144 Bottom 3365 Total Depth of Well 3387 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Lansing-Kansas City</u>	<u>Dry</u>	<u>3144</u>	<u>3365</u>	<u>8-5/8"</u>	<u>272.19</u>	<u>None</u>
				<u>5-1/2"</u>	<u>3391.30</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Cement 3387 to 3345. Set Bridging plug at 3262'. Dumped Calseal to 3258'. Mudded hole 3258' to 240' with Magcogel. Placed 30 sx. cement 240' to base of cellar. Well plugged and abandoned 3:00 P.M. 6-20-52.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
A. T. Slagle (employee of owner) or (conductor/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. T. Slagle
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of June, 19 52

My commission expires November 18, 1953
Joseph P. Deal Notary Public.

23-8390-s 6-51-20M

PLUGGING
FILE SEC 23 T 3 R 19 W
BOOK PAGE 24 LP 13

25 1952 6-25-52
CONSERVATION DIVISION
Wichita, Kansas

15-147-00672-0000

Form No. 875

Formation Record

Lease Hempler

Well No. 4

FROM	TO	Formation	REMARKS
0	20	Shale.	
20	280	Sand and clay.	
280	750	Shale.	
750	815	Sand.	
815	1025	Sand and shale.	
1025	1215	Sand.	
1215	1503	Red Bed.	
1503	1540	Anhydrite.	
1540	2110	Shale and shells.	
2110	2685	Shale and lime.	
2685	2840	Shale.	
2840	2990	Shale and lime.	
2990	3132	Lime.	
3132	3179	Lime and shale.	Top LKC 3144'.
3179	3216	K. C. Lime.	
3216	3387	Lime.	Base LKC 3365'.

RECEIVED
 JUN 25 1952
 MINERAL COMMISSION
 OBSERVATION DIVISION
 Wichita, Kansas

6-25-52

PLUGGING
 FILE SEC 23 T 3 R 190
 BOOK PAGE 24 LINE 13