


15-147-00166-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Phillips County, Sec. 15 Twp. 3 Rge. 19 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW SE  
Lease Owner The Derby Oil Company  
Lease Name Miller "A" Well No. 1  
Office Address 420 West Douglas, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 19  
Application for plugging filed April 9, 1951 19  
Application for plugging approved April 11, 1951 19  
Plugging commenced April 25, 1951 19  
Plugging completed May 2, 1951 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To    | Size   | Put In | Pulled Out |
|-----------|---------|------|-------|--------|--------|------------|
|           |         | 0    | 156'  | 8 5/8" | 156'   | None       |
|           |         | 0    | 3461' | 4 1/2" | 3461'  | 2638       |
|           |         |      |       |        |        |            |
|           |         |      |       |        |        |            |
|           |         |      |       |        |        |            |
|           |         |      |       |        |        |            |
|           |         |      |       |        |        |            |
|           |         |      |       |        |        |            |
|           |         |      |       |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with chat from 3284' to 3260'. Dumped 5 sacks of cement at 3260'.  
Shot pipe off at 2638'. Pulled pipe and mudded hole to 150'. Set rock  
bridge at 150' and dumped 15 sacks of cement. Mudded hole to 30' and put  
10 sacks of cement at top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to The Derby Oil Company  
Address P. O. Box 1030, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
F. W. Heiser (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) F. W. Heiser, Exploitation Engineer  
Box 1030, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 51

H. A. Bilson, Notary Public.

My commission expires August 24, 1953

PLUGGING  
FILE SEC 15 T 3 R 19a  
BOOK PAGE 72 LINE 43

COMPANY:

THE DERBY OIL COMPANY  
HEXAGON OIL COMPANY

Rotary Drilling Commenced: 2/23/51  
Rotary Drilling Completed: 3/9/51

LOCATION:

SE SW SE, MILLER "A" #1  
Sec. 15-35-19W, Phillips County, Kansas

15-147-00166-00-00

CONTRACTOR:

PICKRELL DRILLING COMPANY, INC.  
Wichita, Kansas

CASING RECORD:

156' (5 Jts.) 8 5/8" new seamless 24# J-55 casing set at 156' in a 12 1/4" hole, cemented with 85 sac cement.

3461' (121 Jts.) 4 1/2" 11.60# casing set at 3461' in a 7 7/8" hole, cemented with 125 sac cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

|                            |                  |                                |
|----------------------------|------------------|--------------------------------|
| Cellar                     | 5                | Circulate for samples at 3222' |
| Shale & Shells             | 400              | " " " " 3270'                  |
| Shale, Shells & Sand Strs. | 720              | " " " " 3290'                  |
| Sand & Shale               | 900              | " " " " 3408'                  |
| Shale, Shells & Sand Strs. | 1325             | " " " " 3463'                  |
| Shale & Shells             | 1375             |                                |
| Partise Iron               | 1405             | Slope test at 1000' - 0° off.  |
| Shale & Anhydrite          | 1610             | " " " 1500' - 0° off.          |
| Anhydrite                  | 1620             | " " " 2000' - 0° off.          |
| Shale & Shells             | 1975             | " " " 2500' - 0° off.          |
| Shale, Shells & Sand Strs. | 2250             | " " " 3000' - 0° off.          |
| Broken Lime                | 2360             |                                |
| Lime & Shale               | 3045             | S.L.M. at 2000' - O.K.         |
| Lime                       | 3463 Rotary T.D. | " " 3250' - O.K.               |
|                            |                  | " " 3463' - O.K.               |

The undersigned, G. W. Sebitts, Secretary of PICKRELL DRILLING COMPANY, INC., hereby certifies in behalf of said corporation, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY, INC.

RECEIVED  
REGISTRATION COMMISSION

Secretary

STATE OF KANSAS

SS

MAY 22 1951

5-22-51

COUNTY OF SENNICK

REGISTRATION DIVISION  
Wichita, Kansas

BE IT REMEMBERED that on this 22nd day of March, 1951, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came G. W. Sebitts, Secretary of Pickrell Drilling Company, Inc. a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

*Ethel Zimmerman*  
Notary Public

My commission expires January 28, 1953.

PLUGGING  
FILE SEC 15 T3 R19W  
BOOK PAGE 72 LINE 43