


15-147-19083-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 14 Twp. 3 Rge. 19W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE NE
Lease Owner Imperial Petroleum Company, Inc.
Lease Name Vogel Well No. 2
Office Address 903 Union National Bank Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 22 19 50
Application for plugging filed December 18 19 52
Application for plugging approved December 22 19 52
Plugging commenced December 24 19 52
Plugging completed December 28 19 52
Reason for abandonment of well or producing formation unable to produce oil
in commercial quantities
If a producing well is abandoned, date of last production December 15 19 52
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing-Kansas City Depth to top 3127 Bottom 3188 Total Depth of Well 3188 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3177'	1996'
				8 5/8"	152'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 3182' to 3130' and ran
4 sacks of cement. Set rock bridge from
150' to 140' and ran 15 sacks of cement.
Mudded hole to 40', set rock bridge to 25'
and ran 10 sacks of cement. Plugging
completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL DRILLING COMPANY, INC.

(Signature) By: Raymond L. Bacon Vice-Pres.
903 Union National Bank Bldg.,
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 53

My commission expires 1-4-54
Marguerite Tuttle
Notary Public.

24-2675-S 2-52-20M



2-4-53

IMPERIAL OIL COMPANY, INC.
VOGEL # 2

NE SE NE Sec. 14-3S-19W
Phillips County, Kansas

Total Depth: 3182
Comm: 12-14-50
Comp: 12-22-50

<u>Casing</u>	<u>Cement</u>
8 5/8" set @ 152'	90 sacks
5 1/2" set @ 3177'	100 sacks

<u>Formation</u>	<u>Depth</u>
Shale & sand	0 - 75
Sand & blue shale	75 - 154
Sand & shale	154 - 745
Sandy shale	745 - 1030
Dakota sand	1030 - 1210
Shale & shells	1210 - 1400
Red bed & shells	1400 - 1493
Anhydrite	1493 - 1530
Shale	1530 - 1710
Shale and shells	1710 - 2100
Shale & lime	2100 - 2995
Lime, shale, chert	2995 - 3065
Lime	3065 - 3182

Total Depth - 3182'

STATE OF KANSAS }
SEDGWICK COUNTY } SS

We hereby certify that the above information is true and correct to the best of our knowledge.

IMPERIAL DRILLING COMPANY, INC.

By: Raymond J. Bacon
Vice-Pres.

Subscribed and sworn to before me this 16th day of January, 1953.

Marguerite J. Judd
Notary Public

My commission expires:
1-4-54

RECEIVED
JAN 16 1953
Division
Phillips County, Kansas

PLUGGING
SEC 14 T 3 R 19W
BOOK PAGE 47 LINE 4

2-4-53