


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-147-00889-00-01
WELL PLUGGING RECORD



Phillips County. Sec. 13 Twp. 3^S Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines 990 FNL and 330 FWL of NW/4
Lease Owner Phillips Petroleum Company
Lease Name Stuttgart Unit Well No. W-1
Office Address Box 287 - Great Bend, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil-Converted to Input
Date well completed January 18, 19 52
Application for plugging filed April 4, 19 61
Application for plugging approved April 5, 19 61
Plugging commenced May 6, 19 61
Plugging completed May 7, 19 61
Reason for abandonment of well or producing formation Not needed as input

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Input Producing formation LKC Depth to top 3153 Bottom 3376 Total Depth of Well EB 3362 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Silt	Dry	2898		8 5/8"	289	None
Howard	Dry	2911		5 1/2"	3411	1507'
Topeka	Dry	2938				
Base Silt	Dry	3026				
Heebner	Dry	3109				
Toronto	Dry	3134				
LKC	Oil	3153	3376			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand from 3362' to 3125'. Dumped 5 sx. cement to 3085'. Shot casing at 1510'. Mudded hole from 3085' to 500'. Dumped 40 sx. cement to 130'. Mudded hole to 35'. Dumped 10 sx. cement in filling to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1961
05-11-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. E. Michael (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *M. E. Michael*
Box 287 - Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of May, 19 61

My commission expires 11/18/61

Joseph M. Beal
Notary Public.

EXPLORATION RECORD

Lease Stuttgart Unit

Well W-1

Formation Name	Top	Base	Remarks
Surface Soil	0	10	
Broken Lime	10	60	
Shale	60	245	
Shale and Shells	245	300	
Blue Shale and Shells	300	570	
Shale and Sand	570	945	
Sand and Redrock	945	1095	
Sand - Shells - Shale	1095	1485	
Annydrite	1485	1535	
Redbed and Shale	1535	1750	
Shale and Shells	1750	1850	
Shale and Lime Streaks	1850	1990	
Shale and Shells	1990	2095	
Lime and Shale	2095	2160	
Lime	2160	2216	
Lime and Shale	2216	2580	
Lime	2580	2630	
Lime and Shale	2630	2765	
Lime	2765	2800	
Lime and Shale	2800	3056	
Lime	3056	3390	
			Tops:
			Silt 2898
			Howard 2911
			Topeka 2938
			Base Silt 3026
			Heebner 3109
			Toronto 3134
			LKC 3153
			Base LKC 3376

RECEIVED
STATE COMMISSION

MAY 11 1931

CONSERVATION DIVISION
Wichita, Kansas