


15-147-00896-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 14 Twp. 3 Rge. 19W (E).....(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NE
Lease Owner Imperial Petroleum Company, Inc.
Lease Name Vogel Well No. 4
Office Address 903 Union National Bank Bldg., Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 19 19 51
Application for plugging filed December 18 19 52
Application for plugging approved December 22 19 52
Plugging commenced January 2 19 53
Plugging completed January 6 19 53
Reason for abandonment of well or producing formation unable to produce oil
in commercial quantities.
If a producing well is abandoned, date of last production December 15 19 52
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing-Kans. City Depth to top 3116 Bottom 3250 Total Depth of Well 3250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	3227'	2232'
				8 5/8"	175'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Sanded hole from 3227' to 3125'. Mudded hole to 175', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 35', set rock bridge to 28' and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God IMPERIAL DRILLING COMPANY, INC.

(Signature) By [Signature] Vice-Pres.
903 Union National Bank Building
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of February, 19 53


My commission expires January 4, 1954
Notary Public.

23-8390-s 6-51-20M

FEB 4 - 1953

CONSERVATION DIVISION
Wichita, Kansas

2-4-53



IMPERIAL PETROLEUM COMPANY, INC.
VOGEL # 4

SW SE NE Sec. 14-38-19W
Phillips County, Kansas

Total Depth: 3227'
Comm: 1/9/51
Comp: 1/19/51

<u>Casing</u>	<u>Cement</u>
8 5/8" Set @ 175'	125 sacks
5 1/2" Set @ 3227'	125 sacks

<u>Formation</u>	<u>Depth</u>
Sand shells	0 - 120
Shale shells	120 - 405
Shale & shells	405 - 690
Sand	690 - 800
Shale & shells	800 - 1460
Shale shells	1460 - 1470
Anhydrite	1470 - 1515
Shale shells	1515 - 1660
Shale & lime streaks	1660 - 1990
Shale shells	1990 - 2170
Shale & lime	2170 - 2350
Shale shells	2350 - 2415
Shale & lime	2415 - 2600
Shale shells	2600 - 2690
Shale & lime	2690 - 3020
Lime & shale streaks	3020 - 3060
Lime	3060 - 3227

STATE OF KANSAS }
SEDGWICK COUNTY } SS

We hereby certify that the above information is true and correct to the best of our knowledge.

IMPERIAL DRILLING COMPANY, INC.
By: Raymond L. Bacon
Vice-Pres.

Subscribed and sworn to before me this 16th day of January, 1953.

Marquette Little
Notary Public

My Commission Expires:

1-4-54

NOTARY PUBLIC
FEB 4 - 1953
OIL & GAS COMMISSION
SEDERVATION DIVISION
Topeka, Kansas

PLUGGING
FILE 38-147-3-19W
BOOK PAGE 67 LINE 6

2-4-53