

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

16
WELL PLUGGING RECORD

15-147-00671-00-01

Phillips County, Sec. 14 Twp. 35 Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines C S/2 NW SE
Lease Owner Phillips Petroleum Company
Lease Name Stuttgart Unit Well No. W-2
Office Address Box 287 - Great Bend, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil-Converted to Input
Date well completed May 29, 19 52
Application for plugging filed April 17, 19 61
Application for plugging approved May 1, 19 61
Plugging commenced May 8 19 61
Plugging completed May 8, 19 61
Reason for abandonment of well or producing formation Not needed as input



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Input ~~producing~~ formation LKC Depth to top 3100 Bottom 3322 Total Depth of Well PB 3316 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Howard	Dry	2857		8 5/8"	283.70	None
Topeka	Dry	2885		5 1/2"	3364.05	None
Heebner	Dry	3058				
Toronto	Dry	3081				
LKC	Oil	3100	3322			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Shot casing at 2100' and 1850', would not take fluid. Shot at 1497', pumped in 10 sx. mud at 1000# and 65 sx. cement in filling to base of cellar. Well Plugged and abandoned at 1:00 PM, 5/8/61

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1961
05-11-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company

Address Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. E. Michael (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael
Box 287 - Gt. Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 61

My commission expires 11/18/61 Joseph M. Beal Notary Public.



EXPLORATION RECORD

15-147-00671-00-01

Lease Stuttgart Unit

Well W-2

Formation Name	Top	Base	Remarks
Sand and shale	0	990	
Sand	990	1177	
Shale and Red Bed	1177	1450	
Red Bed	1450	1465	
Anhydrite	1465	1505	
Shale and Shells	1505	2065	
Shale and Lime	2065	2515	
Shale	2515	2640	
Shale and Lime	2640	2760	
Lime	2760	2835	
Lime and Shale	2835	2918	
Lime	2918	3196	
Lime and Shale	3196	3253	
Lime	3253	3306	
Lime and Shale	3306	3338	

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1961
CONSERVATION DIVISION
Wichita, Kansas