



15-147-00440-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Paul Dean of Phillips Petroleum Co. has this date requested permission to plug the following described well:

Operator's Full Name: Phillips Petroleum Co.

Complete Address: Box 287 - Neat Bend, Ks 67530

Lease Name: Wisman A Well No. 1

Location: C-SE/4-SE4 Sec. 2 Twp. 3 Rge. 19 (E) (W)

County: Phillips Total Depth: 3248

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Dean was instructed to plug the well as follows:

8 5/8" @ 61 w/circ cmt. 5 1/2" - #14 - w/100 oz @ 3196 -  
3248 open hole - perp @ 3126-82 Hole in casing @ 1018 +  
1060' - Cast Plug 2975 w/50' sand + 5 oz cmt. - Recovered  
930' of 5 1/2 casing Ordered 140 oz 50/50 polymer 6 % gel  
3 % CC - 20 gel - 5 hulls + 8 5/8 plug Pumped in 4 hulls  
→ 8 gel → 1 hull → 70 cmt → 12 gel → 70 cmt Max  
PSI 900 #

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION  
7-20-82  
JUL 20 1982

Dennis L. Hamel  
Conservation Division Agent