



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

API # 15-147-20,350-00-00

Dear Sir:

Mr. Laudy Herman of Thunderbird Drilling has this date requested permission to plug the following described well:

Operator's Full Name: Thunderbird Drilling Inc.

Complete Address: 7701 E. Kellogg, Suite 780, Box 18407, Wichita, Kansas

Lease Name: Wells Well No. 1

Location: NW-SW Sec. 3 Twp. 3 Rge. 19 (E)

County: Phillips Total Depth: 3635

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Herman was instructed to plug the well as follows:

8 1/2" - 327' SP - circ cnt w/ 250 sk common 2% gel - 3% CA-Cl (allied)
Ordered 130 sk 50% pozmix 4% gel, 3% CA-Cl + 8 1/2" Plug
1st-Plug @ 960' w/ 70 sk cnt
2nd-Plug @ 300' w/ 40 sk cnt (cont'd by Allied)
3rd-Solid bridge-bulldog plug @ 40' to 0' w/ 10 sk
Rat-hole - 10 sk - Spot w/ drill stem - heavy mud between
all plugs!

11:15 RECEIVED
1-27-82

Very truly yours,

Dennis L. Hamel
Conservation Division Agent