

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
September 2003  
Form must be Typed  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15- 111'-20427-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 9/5/03

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549

Address: 1201 Lake Robbins Drive (Owner/Company Name) City: The Woodlands (Operator's)

State: TX Zip Code: 77380 Contact Phone: 832 636-3128

Lease: Briggs Well #: 1-5 Sec. 5 Twp. 17 R. 13  East  West

CE/2 - NE Spot Location/QQQQ County Lyon

1320 Feet from (in exact footage)  North /  South (from nearest outside section corner) Line of Section (not Lease Line)

660 Feet from (in exact footage)  East /  West (from nearest outside section corner) Line of Section (not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 9-5/8" Set at: 241' Cemented with: 180 Sacks

Production Casing Size: 7" Set at: 2764' Cemented with: 330 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 1856' -1857', 1908' -1910', 1942' -1944'.

Elevation: 1139' ( G.L.  K.B.) T.D. 2770' PBD 2722' Anhydrite Depth \_\_\_\_\_ (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Place 2 sxs hulls and 30 sxs cement to cover perfs. Cut off 7" casing at 1200'. Spot 20 sxs cement from 1150' -1200'. Pump 120 sxs Class H cement from surface down. Cut off and cap 9-5/8" casing at 4' below GL. Space heavy mud between cement plugs.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Micheal Pond Phone: 620 482-1006

Address: 1707 W 2nd Street City/State Liberal, KS 67901

Plugging Contractor Eagle Well Service KCC License # 7407  
(Company Name) (Contractor's)

Address 1661 W. 7th, Liberal, KS 67901 Phone: 620 624-1904

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-2-04 Authorized Operator / Agent: Jerry N. Blossom (Signature)  
Jerry N. Blossom

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 03 2004

CONSERVATION DIVISION  
WICHITA, KS

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

August 03, 2004

Re: BRIGGS #1-5  
API 15-111-20427-00-00  
E2NE 5-17S-13E, 1320 FNL 660 FEL  
LYON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #3  
1500 W. 7th  
Chanute, KS 67220  
(620) 432-2300

Sincerely  


David P. Williams  
Production Supervisor