

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
September 2003
Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15- 197-20265 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 9/17/03

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549

Address: 1201 Lake Robbins Drive (Owner/Company Name) City: The Woodlands (Operator's)

State: TX Zip Code: 77380 Contact Phone: 832 636-3128

Lease: Thompson Well #: 1-33 Sec. 33 Twp. 13 R. 13 East West

CW/2 - E/2 - NE Spot Location/QQQQ County Wabaunsee

1320 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

990 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 9-5/8" Set at: 364' Cemented with: 190 Sacks

Production Casing Size: 7" Set at: 3057' Cemented with: 265 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf: 1904-1905', 2016-2017', 2141-2143', 2230-2232'

Elevation: 1306' (G.L. K.B.) T.D. 3065' PBDT 3015' Anhydrite Depth _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP @ 1890'. Dump 2 sxs cement on CIBP Cut off 7" casing @1200'. Spot 20 sxs cement from 1150'-1200'. Pump 170 sxs Class H cement from surface down. Cut off and cap 9-5/8" casing at 4'. Space plugs with heavy muds.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log submitted with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Micheal Pond Phone: 620 482-1006

Address: 1707 W. 2nd Street City/State Liberal, KS 67901

Plugging Contractor Eagle Well Service KCC License # 7407
(Company Name) (Contractor's)

Address 1661 W. 7th Street, Liberal, KS 67901 Phone: 620 624-1904

Proposed Date and Hour of Plugging (If known?): _____

RECEIVED
KANSAS CORPORATION COMMISSION

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-2-04 Authorized Operator / Agent: Jerry N. Blossom

AUG 03 2004

(Signature)

Jerry N. Blossom

CONSERVATION DIVISION
WICHITA, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

August 03, 2004

Re: THOMPSON #1-33
API 15-197-20265-00-00
W2E2NE 33-13S-13E, 1320 FNL 990 FEL
WABAUNSEE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300

Sincerely

David P. Williams
Production Supervisor