

15-147-20277-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Phillips SEC. 31 TWP. 3 RGE. 19W E/W  
Location as in quarters or footage from lines:  
430' FEL & 330' FSL NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner American Petroleum Company, Inc.  
Lease Name Zilligner #1 Well No. \_\_\_\_\_  
Office Address Suite 111 400 N. Woodlawn, Wichita, Kansas 672-8  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 7-16-81  
Plugging completed 7-21-81  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3591'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	240'	none
				4 1/2"	3587'	1196'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Moved in on location and got 9" stretch. Plugged bottom with 1 barrel sand,  
and 4 sacks cement. Shot and worked pipe @2802', 2588', 2412', 2214', 2007', 1803',  
1597', 1394' and 1205'. Pulled 37 joints. Plugged well with 30 sacks gel, 5 sacks hulls,  
8-5/8" plug, 140 sacks 50/50 pos 4% gel 3% CC. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
R. Darrell Kelso  
(Address)

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of July, 1981

My Commission expires:



Joan Kelso  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
7-29-81  
291981  
CONSERVATION DIVISION  
Wichita, Kansas