

State Corporation Commission
Conservation Division
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

PLUGGING RECORD
C.A.R.-82-3-117

API NUMBER 15-147-20,272-00-00

LEASE NAME Vogel

WELL NUMBER B-1

1550 Ft. from S Section Line

3040 Ft. from E Section Line

SEC. 26 TWP. 3 RGE. 19 (E) or (W)

COUNTY Phillips

Date Well Completed 5-16-80

Plugging Commenced 12-10-96

Plugging Completed 12-10-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc

ADDRESS Box 428 Logan, KS 67646

PHONE# (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-17-96 (date)

by Dennis Hamel - Hays (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation KC Depth to Top 3212 Bottom 3234 T.D. 3420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
-	SAND + shale	Surface	248'	8 5/8	248	None
-	Shale + limestone	Surface	3419	4 1/2	3419	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Pumped 25 sacks of cement with 2 sack hails followed by 10 sacks of gel followed by 100 sacks cement. Max pressure 500* shut-in at 200 PSI.
Tied on backsides of 8 5/8 and pumped 1 sack haul with 25 sacks cement, Max pressure 400 PSI and 100 PSI ZEP. Note: prior to cementing well was perforated at 1540 and 980'

Name of Plugging Contractor Allied Cementing Co. Inc License No. _____

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co Inc


STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R Baird

(Address) Box 428 Logan KS 67646



before me this 11th day of DECEMBER, 19 96

Robert B. Hartman
Notary Public

My Commission Expires: 3/29/99

USE ONLY ONE SIDE OF EACH FORM