

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-20,060-00-00

LEASE NAME VEEH

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1650 Ft. from S/N Line of Section (circle one)

330 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR ANDERSON ENERGY INC.

SPOT LOCATION se - sw - se -

ADDRESS 200 E. First St. Suite 414

SEC. 26 TWP. 3S S. RGE 19 W (E) or (W)

CITY, STATE, ZIP Wichita, Ks. 67202

COUNTY Phillips

PHONE# 16 265-7929 OPERATORS LICENSE NO. 6484

Date Well Completed N/A

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 8-5-98

Date Plugging Completed 8-5-98

The plugging proposal was approved on 7-28-98 (date)

by Herb Deines / Dist#4 (KCC District Agent's Name)

Is ACO-1 filed? Unknown If not, is well log attached? Copy was sent.

Producing Formation(s) LKC Depth to Top 3246' Bottom 3284' T.D.P.B. 3405'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULL OUT |
|-----------|-----------|------|-------|------|--------|----------|
| G1 - 219' | shale/sd | 0' | 219' | 7" | 219' | N/A |
| LKC | lmst,shle | 0' | 3441' | 4.5 | 3441' | N/A |
| | | | | | | |
| | | | | | | |

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from Surf feet to 3405' feet each set.

Open ended tbg to 3030', Mixed 100 sks cmt w/300 hulls, pull tbg 1530' mixed and circulated to surf, using 85 sks and 200 hulls. filled csg w/15 sks, Put 50 sks down annulus, 100 psi standing. csg still full.

Used total of 250 sks 60/40 10% gel, and 500# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor EXPRESS Well Service.

License No. 6426

Address Box 426, Victoria, Ks. 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: William L. Anderson

STATE OF Kansas COUNTY OF Phillips, ss.

Robert A. wahlmeier Agent (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Robert A. wahlmeier

(Address) 2213 Virginia Drive Hays, Ks. 67601-2337

SUBSCRIBED AND SWORN TO before me this 18 day of Aug, 19 98

Rebecca A. Claycamp
Notary Public

My Commission Expires: 10-12-98



RECEIVED
KANSAS CORP COM
AUG 20 12 33
8-20-98