

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-177

API NUMBER 15-147-20,457-00-00

LEASE NAME Grau B

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3

330 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR R.P. Nixon Operations, Inc.

SEC. 35 TWP. 3S RGE. 19W (E) or (W)

ADDRESS 207 West 12th Street Hays, KS 67601

COUNTY Phillips

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Date Well Completed 9-22-84

Character of Well Injection E-23,647

Plugging Commenced 10-26-94

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

Plugging Completed 10-26-94

The plugging proposal was approved on 10-26-94 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 Filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L/KC Depth to Top 3212' Bottom 3409' T.D. 3450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	200'	None
				4 1/2"	3448'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Ran tubing to 2512' Pumped down tubing w/50 sx common & 100# hulls and circulated to surface. Pulled tubing to 1575' and pumped 80 sx of 60/40 Poz., 10% gel & 100# hulls. Cement circulated. Pulled tubing from hole and tied on to casing and pumped 20 sx of same blend. ISIP: 700#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corp. License No. 5128

Address 207 West 12th St. Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Oper. Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 207 W. 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 94

[Signature]  
Notary Public

My Commission Expires: 5-24-97



Rec'd  
11-30-94