

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20957-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 30-22S-9W
4620 feet from S Section Line, 5000 feet from E Section Line
Lease Name: SLEEPER A Well #: 1-30
County: RENO Total Vertical Depth: 3752 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3752
SURF Size: 8.625 feet: 259

\$ 121⁹⁴

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/07/2004 4:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Could not get past 2775' -- 5 sxs of cement and 20' of sand. 1325' - 35 sxs; 850' - 35 sxs; 310' - 0'

RECEIVED
KCC DISTRICT #2
JUL 13 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2004 8:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Perfs:

Shot 4-1/2" casing off at 2003'. Pulled to 1325' and pumped 35 sacks of cement. Pulled to 850' and pumped 35 sacks of cement. Pulled to 310' and circulated cement to surface. Put 200 lbs of cotton hulls at both bottom plugs.

60/40 posmix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID & CEMENT #23557

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

8-5-04

INV. NO.

200-5060282