

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19490-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 29-26S-7E  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: GUENTHER Well #: B3  
County: BUTLER Total Vertical Depth: 2787 feet

Operator License No.: 5387  
Op Name: BUCKEYE CORP., AZTEC OIL CO. DIVI  
Address: PO BOX 1020  
EL DORADO, KS 67042

PROD Size: 4.5 feet: 2720 30 SX CMT  
SURF Size: 7 feet: 2752 30 SX CMT

\$90<sup>58</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2004 12:00 PM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING  
Proposal Revd. from: STEVEN W. KILE Company: BRADEN PETROLEUM & WELL PL Phone: (316) 321-6690

Proposed Sand to 2700' & 4 sxs; circ thru 7" @ 250' to surf; cement inside & outside 7".  
Plugging Method:

RECEIVED  
KCC DISTRICT #2  
AUG 4 - 2004

Plugging Proposal Received By: MICHAEL WILSON  
Date/Time Plugging Completed: 07/29/2004 3:20 PM

WitnessType: PARTIAL  
KCC Agent: BILL JOHNSON

WICHITA, KS

Actual Plugging Report:

Sanded to 2700' with 4 sacks of cement; 7" @ 210'.  
7/22/2004 -- Cement through 1" poly tubing from 250' - 150' with 250 sacks of cement; oil to surface; ran out cement. 60/40 posmix with 4% gel.  
7/28/2004 -- Cement in casing 150'; Rain out job.  
7/29/2004 -- 1" poly tubing 150' on outside; cement to surface. 1" poly pipe to 150'; inside 7" cement to surface. 210 sacks.  
460 sacks total.

Perfs:

Top	Bot	Thru	Comments
2752	2787		

RECEIVED  
AUG 05 2004  
KCC WICHITA

Remarks: PLUGGED THROUGH CASING AND TUBING

Plugged through: CSG

District: 02

Signed

Bill Johnson  
(TECHNICIAN)

INVOICED

DATE

8-5-04

INV. NO.

2005060284