

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23411-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 36-19S-25W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: WESLEY Well #: 1
County: NESS Total Vertical Depth: 4427 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: RR 1, BOX 183 B
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 4422 WITH 165 SX CMT
SURF Size: 8.625 feet: 800 WITH 300 SX CMT

88
\$143

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE Company: DAVIS PETROLEUM Phone: (620) 793-3051

Proposed Plugging Method: RUN TUBING TO 4400' & PUMP 20 SX CMT & 200# HULLS. PLUG AT 1800' WITH 30 SX CMT. PLUG AT 800-0'.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 07/22/2004 3:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SQUEZZED @ 1056-1118' WITH 250 SX CMT. SQUEEZED @ 3153-3185' WITH 150 SX CMT. RUN TUBING TO 4247' & PUMPED 25 SX CMT & 100# HULLS. 1ST PLUG PULL TUBING TO 1800" & PUMPED 30 SX CMT. 2ND PLUG PULL TUBING TO 800' & CIRCULATED CMT TO SURFACE WITH 60 SX CMT. 3RD PLUG PULLED TUBING & TOPPED OFF WITH 20 SX CMT. STAYED FULL. TIED ONTO BACKSIDE & PUMPED 1/4 BBL WATER AND PRESSURED TO 500# AND HELD.

Perfs:


Top	Bot	Thru	Comments
4422	4427	OH	

RECEIVED
AUG 05 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael J. Maier
(TECHNICIAN)

INVOICED

DATE

8-5-04

INV. NO.

2005060285

Form 6P-2/3