

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22870-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 36-18S-24W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LEHNER Well #: 1
County: NESS Total Vertical Depth: 4332 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: RR 1, BOX 183 B
GREAT BEND, KS 67530

MSCC Size: feet: 1484 CMT TO SURFACE
PROD Size: 4.5 feet: 4332 WITH 250 SX CMT
SURF Size: 8.625 feet: 212 WITH 140 SX CMT

\$140⁷⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE KASSELMAN Company: DAVIS PETROELUM Phone: (620) 793-3051

Proposed Plugging Method: PUMP 50 SX CMT & 300# HULLS. PUMP GEL & CMT. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2004 10:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PORT COLLAR @ 1484' CEMENTED TO SURFACE. PUMP 50 SX CMT & 300# HULLS. PUMP 14 SX GEL & 100 SX CMT. MAXIMUM PRESSURE 1200#. SHUT IN PRESSURE 700#. TIED ONTO BACKSIDE & PUMP 1/4 BBL WATER. PRESSURED TO 500# AND HELD.

RECEIVED
AUG 05 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
4281	4283		
4266	4273		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
JUL 29 2004
KCC Dodge City

Signed Michael Maier
(TECHNICIAN)

INVOICED
DATE 8.5.04
INV. NO. 2005060285

Form CP-2 *[Signature]*