

4-032000

10-25

E-23,647

API number: 15-147-20,457-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW /4 SEC. 35, 03 S, 19 W
330 feet from S section line
4950 feet from E section line

Operator license# 5252 Lease Grau "B" well # 3

Operator: R.P. Nixon, Inc. County Phillips

Address: 207 West 12th Street Well total depth 3448 feet *112.06*
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well ____, Gas well ____, Input well X, SWD ____, D & A ____

Plugging contractor: Jay-Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 25 Month: October Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon, Inc. Phone: _____

Were: Order 325 sxs. 60/40 pozmix - 10% gel - 50 sxs. common cement.
Order work string of tubing.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 25, Month: October, Year: 94

Actual plugging report: 8 5/8" set at 200' w/135 sxs. cwc. 4 1/2" set @
3448' w/125 sxs. Prod. perfs. 3251' - 3379'. Perf. 4 1/2" at 1600' cwc.
Ran tubing to 2500' - displaced 50 sxs. common cement with 100# hulls.
Pulled to 1500' - circulated cement with 80 sxs. with 200# hulls. Pulled
tubing - squeezed 4 1/2" with total 50 sxs. common cement and 100 sxs.
cement blend with 400# hulls mixed in to Max. P.S.I. 700#. Close in
P.S.I. 700#. Tested 8 5/8" to 300# cement visable in head at surface.
Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

Remarks: _____
Condition of casing(in hole): GOOD X BAD _____ Any plug: YES X NO _____
Bottom plug(in place): YES _____, CALC X, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: _____ GL _____

NOV 08 1994

I did [X] / did not [] observe the plugging. Carl Goodrow

INVOICED

(agent)

DATE 11-9-94

Form CP-2/3

INV. NO: 41623
10-25