

4-032004

10-26

00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-147-20,246

NE SW SW /4 SEC. 35, 03 S, 19 W  
990 feet from S section line  
4290 feet from E section line

Operator license# 5252

Lease Grau "B" well # 2

Operator: R.P. Nixon, Inc.

County Phillips

107.35

Address: 207 West 12th Street  
Hays, Kansas

Well total depth 3303 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Jay-Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 26 Month: October Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon, Inc. Phone:           

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:30A.M., Day: 26, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 218' w/150 sxs. 5 1/2" set @ 3222'  
w/250 sxs. O.H. 3222' - 3303'. Critical control area shots at 925' and  
1500'. Squeezed 5 1/2" with 250 sxs. cement blend with 500# hulls mixed  
in to Max. P.S.I. 300#. Close in P.S.I. 100#. 8 5/8" squeezed with  
25 sxs. to Max. P.S.I. 200#. Close in P.S.I. 100#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 08 1994

11-8-94

CONSERVATION DIVISION

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:            GL

I did     observe the plugging.

Carl Goodrow

**INVOICED**

MD

(agent)

DATE 11-9-94

Form CP-2/3

INV. NO: 41622

10-26