

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22261-00-00
Spot: SENWSW Sec/Twnshp/Rge: 32-12S-21W
1530 feet from S Section Line, 1110 feet from W Section Line
Lease Name: SCHOENTHALER Well #: 1-32
County: TREGO Total Vertical Depth: 4041 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

SURF Size: 8.625 feet: 224

#131³³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/22/2004 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 07/22/2004 1:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3950' w/25 sxs.
2nd. Plug at 1750' w/25 sxs.
3rd. Plug at 950' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
AUG 02 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

JUL 30 2004

INVOICED

DATE

8.5.04

INV. NO.

2005060288