

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22947-00-00
Spot: SENE SW Sec/Twnshp/Rge: 18-21S-11W
1700 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RADER B Well #: 2-18
County: STAFFORD Total Vertical Depth: 3640 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

PROD Size: 5.5 feet: 3625 WITH 175 SX CMT
SURF Size: 8.625 feet: 279 WITH 225 SX CMT

\$ 118 30

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2004 11:20 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3480' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40 WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND
Date/Time Plugging Completed: 07/27/2004 12:45 PM

Witness Type: COMPLETE (100%)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND TO 3546' WITH 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3530	3536		

RECEIVED
AUG 05 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2520' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JUL 29 2004
KCC Dodge City

Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE

8-5-04

IN. NO.

2005060293

Form CP 2/5