

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-20060-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 27-23S-4W  
300 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HILL Well #: 3  
County: RENO Total Vertical Depth: 3391 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N, STE1010D PO BOX  
WICHITA, KS 67275

PROD Size: 4.5 feet: 3388 100 SX CMT  
SURF Size: 8.625 feet: 583 100 SX CMT

\$110<sup>21</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2004 8:00 AM  
Plug Co. License No.: 5118 Plug Co. Name: TGT PETROLEUM CORPORATION  
Proposal Rcvd. from: HAROLD BELLERIVE Company: TGT PETROLEUM CORPORATION Phone: (316) 773-2266

Proposed Plugging Method: Sand to 3,175' & spot 4 sxs. cement. Perforate 4 1/2" casing @ 635' & 325'. Run 2 3/8" tubing to 635' & spot 50 sxs. cement. Pull tubing to 325' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2004 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

C.I.B.P. @ 3,235'. Ran 2 3/8" tubing to 3,050' & spotted 50 sxs. cement. Pulled tubing. Perforated 4 1/2" casing @ 635' & 325'. Ran tubing to 656' & spotted 50 sxs. cement w/ 3% CaCl. Pulled tubing & W.O.C. Ran tubing & tagged cement @ 1,400'. Pulled tubing to 656' & spotted 50 sxs. cement w/ 3% CaCl. W.O.C. Ran tubing & tagged cement @ 1,390'. Circulated 150# of hulls - all annuluses circulated. Tried to build bridge @ 740' w/ rocks & wood - 4 1/2" bridged off @ 40'. Used power swivel & pump to drill to 656'. Spotted 50 sxs @ 656'. Circulated 150 sxs. cement from 325' to the surface. 07/01/04 - Ran 1" tubing between 8 5/8" & 4 1/2" casing to 84' & circulated 25 sxs. cement to the surface.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3335 | 3340 |      | CSG      |

RECEIVED  
KCC DISTRICT #2  
JUL 27 2004  
WICHITA, KS

RECEIVED  
AUG 05 2004  
KCC WICHITA

Remarks: USED 60/40 POSMIX W/ 4% GEL BY ACID SERVICES. INVOICE #8593.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 8-5-04  
INV. NO. 2005060303