

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21097-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 5-30S-18W
3680 feet from S Section Line, 1050 feet from E Section Line
Lease Name: PARKIN E Well #: 1
County: KIOWA Total Vertical Depth: 5039 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

PROD Size: 5.5 feet: 5039 WITH 250 SX CMT
SURF Size: 8.625 feet: 431 WITH 150 SX CMT

\$163⁷⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4900' WITH 4 SX CMT. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2004 1:10 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SAND TO 4900' WITH 5 SX CMT ON TOP. PERFORATE CASING AT 1000'. COULD NOT PUMP INTO AT 700#. 1ST PLUG PULL TO 450' & SPOT 50 SX CMT. 2ND PLUG PULL TO 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4968	4973		

RECEIVED
AUG 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

[Handwritten Signature]

(TECHNICIAN)

INVOICED

DATE 8-5-04

INV. NO. 2005060306

Form SP-213

[Handwritten Signature]