

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20893-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 19-27S-15W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: FRUIT Well #: 4  
County: PRATT Total Vertical Depth: 4584 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 125 N. MARKET, STE 1075  
WICHITA, KS 67202

PROD Size: 5.5 feet: 4584 WITH 200 SX CMT  
SURF Size: 8.625 feet: 367 WITH 150 SX CMT

*\$148<sup>98</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2004 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4270' & 5 SX CMT. PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/22/2004 4:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SAND TO 4270' WITH 5 SX CMT. 1ST PLUG PULL CASING TO 1000' & SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 390' & PUMP 50 SX CMT. 3RD PLUG PULL TO 40' & PUMP 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4576	4582		
4314	4319		

RECEIVED  
AUG 04 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*[Signature]*  
(TECHNICIAN)

INVOICED

DATE 8-5-04  
INV. NO. 2005060306

Form CP 2/3

*[Signature]*