

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-00037-00-01  
Spot: NESESE Sec/Twnshp/Rge: 30-8S-26W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SUTOR Well #: 1  
County: SHERIDAN Total Vertical Depth: 1400 feet

Operator License No.: 5145

SURF Size: 8.625 feet: 236

Op Name: DREILING OIL INC

Address: PO BOX 550 1008 CODY AVE  
HAYS, KS 67601

\$45<sup>50</sup>

Well Type: DH

UIC Docket No:

Date/Time to Plug: 07/27/2004 12:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC.

Proposal Rcvd. from: TERRY PIESKER

Company: DREILING OIL, INC.

Phone: (785) 625-8327

Proposed  
Plugging  
Method:

Ordered 150 sxs cement.

Plugging Proposal Received By: DARREL DIPMAN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/27/2004 2:00 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Well was to be drilled out to replug as offset well was intended to be an injection well.  
Pulling unit and power swivel used to get down to 1400' - hit wood/rubber plug.  
Hole started caving in on bit - got to 1400'.  
Ran tubing to 1400' - spotted 25 sxs cement.  
Pulled tubing to 1117' - spotted 25 sxs cement.  
Pulled tubing to 311' - spotted 40 sxs cement.  
Pulled tubing to 40' - circulated with 10 sxs cement - wellbore remained full of cement.  
Total of 100 sxs 60/40 pozmix - 10% gel.

RECEIVED  
AUG 05 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. HOXIE TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L Moses

(TECHNICIAN)

AUG 01 2004

INVOICED

DATE

8-5-04

INV. NO.

2005060290

Form CP-2/3

2606  
 8-28-53  
 9-11-53  
 D & A

GRAHAM-MESSMAN-RINEHART #1 SUTOR 30-8-26N  
 NE SE SE


Contr. \_\_\_\_\_ SHERIDAN County

No. 2606 Comm. 8-28-53 Comp. 9-11-53 W. D & A

Top	Depth	Datum
7 1/4		+378
HEER	371 1/4	-1108
TOR	373 1/2	-1127
LANS	379	-1143
MISS	1272	-1666
TD	1366	-1760

Casing  
 8" 236

DST 3917-29/1.5" 12"  
 MUD, BHP 600#



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS