

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02836-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 5-9S-24W  
4939 feet from S Section Line, 3973 feet from E Section Line  
Lease Name: HOLLEY UNIT Well #: 14-3  
County: GRAHAM Total Vertical Depth: 3930 feet

Operator License No.: 30420  
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR  
Address: 30-38 48TH STREET  
ASTORIA, NY 11103

PROD Size: 5.5 feet: 3923 75 SX CMT  
SURF Size: 8.625 feet: 188 115 SX CMT

*Ø 127<sup>73</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2004 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES, INC. Phone: (785) 625-8360

Proposed  
Plugging  
Method:

Ordered 425 sxs cement and 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/22/2004 10:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2100' and circulated with 130 sxs cement with 500# hulls.  
Pulled all tubing and squeezed 170 sxs cement.  
Max. P.S.I. 900#. S.I.P. 400#.  
Tied to annulus and squeezed 50 sxs cement to 200# P.S.I.  
Blew a hole in casing at braden head.  
Total of 350 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3780	3915		

RECEIVED  
AUG 02 2004  
KCC WICHITA

Remarks: LEASE PREVIOUSLY KNOWN AS WAITE #3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Roger A Moses*

(TECHNICIAN)

INVOICED

DATE 8-5-04

INV. NO. 2005060296

Form CP-2/3

JUL 29 2004

EMPIRE DRILLING

#3 WAITE

5-9-24W  
N2 N2 NW

Contr. EMPIRE DRLG

GRAHAM

County

E 2431 RB Comm.

Comp.

8-16-57

IP 182 BOPD/LANS

PHY POT

Tops	Depth	Datum
ANH	2119	312
HEEB	3711	-1280
TOR	3736	-1305
KC	3752	-1321
TD	3930	-1499

Casing

8" 188

5" 3923

DST 3770-85/1 HR, 1740' G,  
930' O, BHP 1250#

DST 3868-90/1 1/2 HR, 125' WTRY.

SL OC MUD, BHP 700#

DC: RBSO: ACID 3050: SWB 190

BO, NW: SWB 40 BOPH, NW/6 HRS

HOLLEY POOL

1200' OB

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

