

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20117-00-00
Spot: CNENWSE Sec/Twnshp/Rge: 35-3S-19W
2460 feet from S Section Line, 1700 feet from E Section Line
Lease/Unit Name: EMMA Well Number: 1
County: PHILLIPS Total Vertical Depth: 3485 feet

Operator License No.: 3077
Op Name: JOHNSON OIL
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 311 175 sx cmt
Production: Size 4.5 feet: 3480 200 sx cmt \$113.26
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/01/2001 8:00 AM
Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
W.L.M. to 3281'. T.O.F. 300'.
Holes in casing at 900'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/01/2001 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

8 5/8" S.P. - squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 200#.
4 1/2" casing - squeezed 200 sxs cement with 400# hulls.
Max. P.S.I. 600#. S.I.P. 400#.

INVOICED
DATE 5-16-01
WELL NO. 2001061814

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

BOB

MAY 11 2001

PETROLEUM MANAGEMENT, INC. #1 EMMA 35-3-19W
 WICHITA, KS. NE NW SE
 CONTR RED TIGER DRILLING CO. CTY PHILLIPS
 GEOL _____ FIELD VEEH EXT

E 2077 KB CM 3/3/71 CARD ISSUED 5/6/71 IP P 44 BOPD + 12%WTR
 LANS 3255-59, 3292-96
 3368-72, 3412-14, 3438-42 GR 36

API 15-147-20, 117

SMP	TOPS	DEPTH	DATUM
ST CORRAL		1554	+ 523
NEVA		2473	- 396
TOP		2974	- 897
HEEB		3171	-1094
TOR		3198	-1121
LANS		3215	-1138
BKC		3439	-1362
MARM		3460	-1383
CHTY CONG		3557	-1480
ARB		3566	-1489
RTD		3624	-1547

8 5/8" 215/145SX; 4 1/2" 3517/250SX

NO DSTS
 NO LOG
 MICT, PF 3255-3259 1250AC, PF 3292-3296
 1250AC, PF 3368-3372 3750AC, PF 3412-
 3414 1250AC, PF 3438-3442 1250AC, REC LD
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

NO LOG