

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20120-00-00
Spot: CNESENE Sec/Twnshp/Rge: 35-3S-19W
1320 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: GRAU Well Number: 2
County: PHILLIPS Total Vertical Depth: 3461 feet

Operator License No.: 3077
Op Name: JOHNSON OIL
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 339 200 sx cmt
Production: Size 4.5 feet: 3450 125 sx cmt \$112.48
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/01/2001 8:00 AM
Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging Method: Tubing and rods fish at 1487' - sanded in - with holes in casing.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/01/2001 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 1485'. Spotted 90 sxs cement with 400# hulls to circulate at surface.
Pulled tubing and filled casing to surface with 10 sxs cement.
R.U. Cementers to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls mixed in cement.
Max. P.S.I. 100#. S.I.P. 0#.

INVOICED
DATE 5-16-01
INV. NO. 2001061814

RECEIVED
KANSAS CORPORATE COMMISSION
MAY 16 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed

Dennis L Hamel
(TECHNICIAN)

BOB

PETROLEUM MANAGEMENT, INC. #2 GRAU 35-3-19W
 WICHITA, KANSAS NE SE NE

CONTR RED TIGER DRILLING CTY PHILLIPS

GEOL _____ FIELD VEEH

E 2071 KB CM 3/29/71 ^{CARD}ISSUED 7/15/71 IP P 30 BOPD + 10% WTR
 LANS 3253-3374 OA
 GR 39

API 15-147-20,120

SMP	TOPS	DEPTH	DATUM
ST C		1564	+ 507
B FLOR		2188	- 117
WRE		2271	- 200
NEVA		2479	- 408
RED EAGLE		2599	- 528
TAR		2819	- 748
TOP		2983	- 912
HEEB		3173	-1102
TOR		3198	-1127
LANS		3217	-1146
BKC		3441	-1370
RTD		3461	-1390

8 5/8" 345; 5 1/2" 3460/250SX
 DST(1) 3232-60/20-45-20-45, 5' CO, 15'
 OCM, BHP 917-809#, FP 18-36#
 DST(2) 3276-3304/20-45-20-45, 3' CO,
 15' OCM, BHP 1233-1206#, FP 18-36#
 DST(3) 3354-78/20-45-20-45, 15' OIL, 15'
 HOCM, BHP 1151-1079#, FP 18-54#
 MICT, PF 3253-57 AC 1125 & 250 GALS
 KCL WTR, PF 3292-98 AC 1125 & 250 GALS
 KCL WTR, PF 3370-74 AC 1125 & 250 GALS
 KCL WTR, PF

NO LOG

NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS