

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20127-00-01
Spot: NESWNE Sec/Twnshp/Rge: 35-3S-19W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: GRAU Well Number: 3
County: PHILLIPS Total Vertical Depth: 3470 feet

Operator License No.: 3077
Op Name: JOHNSON OIL
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 324 125 sx cmt
Production: Size 4.5 feet: 3469 250 sx cmt \$112.78
Liner: Size feet:

Well Type: EOR UIC Docket No: E16728.1 Date/Time to Plug: 05/01/2001 8:00 AM
Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Wireline measure to 3015' (top perf 3120').
Perf casing at 1600' and 900'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/01/2001 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

5 1/2" casing - squeezed down casing as follows:
25 sxs cement - followed with 175 sxs cement with 400# hulls mixed in cement. Max. P.S.I. 900# S.I.P. 500#.
8 5/8" S.P. - squeezed 50 sxs cement with 100# hulls down surface pipe. Max. P.S.I. 400#. S.I.P. 100#.

INVOICED

DATE 5-16-01

WELL NO. 2001061814

KANSAS CORPORATION COMMISSION

MAY 16 2001

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

BOB

MAY 11 2001

CORRECTED CARD

35-3-19W
NE SW NE

PETROLEUM MANAGEMENT, INC. #3 GRAU

WICHITA, KANSAS
CONTR RED TIGER DRILLING CTY PHILLIPS

GEOL BILL PETERSEN FIELD VEEH

E 2079 KB CM 7/21/71 ^{CARD}ISSUED 10/14/71 IP P 7 BOPD + 22 BWPD
LANS 3253-3372

API 15-147-20.127

SMP	TOPS	DEPTH	DATUM
SC		1555	+ 524
TOP		2977	- 898
HEEB		3172	-1093
TOR		3204	-1125
LANS		3221	-1142
BKC		3441	-1362
ID		3470	-1391

8 5/8" 331/200SX; 4 1/2" 3469/100SX

DST(1) 3237-60/45-60-30-45, REC 80' M W/
SP OIL, BHP 464-446#, FP 45-66#
DST(2) 3260-3302/30-45-30-45, 100' GIP,
3' OIL, 25' HO & GCM, 225' O & GCM
100' 50CMSW, BHP 1072-1049#, FP 134-
179#

MICT, PF 3253-57, 3292-98, 3368-72 AC
3500 REC LD SWB 5BFPH 40% OIL/3HRS, POP

NO LOG

CORRECTED CARD: 10/21/71

LANS WAS: 3321

LANS IS: 3221 (CORR. BY OPERATOR)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS