

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

RECEIVED
APR 26 2004
KCC WICHITA

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-035-21,835-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3-6-78

Well Operator: W. D. SHORT (Owner / Company Name) KCC License #: 6679 (Operator's)

Address: P.O. BOX 729 City: OXFORD

State: KANSAS Zip Code: 67119 Contact Phone: (620) 455-3576

Lease: GROSE-Thompson Well #: 1 Sec 28 Twp. 33 S. R. 5 East West

NE NW SE Spot Location / QQQQ County: Cowley

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # D-21,733 ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 205' Cemented with: 125 Sacks

Production Casing Size: 4 1/2" Set at: 3215' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 1948-68, 2004-34

Elevation: 3215' (G.L. / K.B.) T.D.: 3215 PBTD: 2060 Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand to 1898', 5SKS cement, Shoot off & Pull Casing, Cement from 250' to Surface

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Don Short

Address: P.O. BOX 729 Phone: (620) 455-3576

City / State: OXFORD, KANSAS

Plugging Contractor: Company Rig (Company Name) Company Tools KCC License #: 6679/99998 (Contractor's)

Address: _____ Phone: ()

Proposed Date and Hour of Plugging (if known?): Will Contact, 4/26 - 4/30/2004

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 4-23-2004 Authorized Operator / Agent: Will Short (Signature)

file

DRILLERS LOG

OPERATOR: Zenith Drilling Corporation; Suite 600; 200 W. Douglas; Wichita, KS
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042 67202

Lease Name Grose - Thomson Well No. 1

Sec. 28 T. 33S R. 5E Spot NE NW SE

County Cowley State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 199' with 125 Sxs.

Production: 4 1/2" @ 3215' with 100 Sxs.

Type Well: Oil Total Depth 3215' K.B. _____

Drilling Commenced: 3-2-78 Drilling Completed 3-6-78

Formation	From	To	Tops
Cellar	0	7	
Sand & Lime	7	1020	Kansas City 2555
Shale & Lime	1020	1855	Marmaton 2772
Shale	1855	1940	Mississippi 3127
Sand	1940	2065	
Shale & Sand	2065	2260	
Shale	2260	2365	
Sand & Shale	2365	2555	
Lime	2555	2880	
Shale	2880	3127	
Lime	3127	3215	

RECEIVED
APR 26 2004
KCC WICHITA

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

Initial Production: _____

Electric Log _____ Type and Depths Covered _____

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Short, W.D. d/b/a Short, W. D. Oil Co.
PO Box 1
Oxford, KS 67119

April 28, 2004

Re: GROSE-THOMPSON #1
API 15-035-21835-00-01
NENWSE 28-33S-5E, 2310 FSL 1650 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely



David P. Williams
Production Supervisor