

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15- 081-20547-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 7/26/89

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549
(Owner/Company Name) (Operator's)

Address: 1201 Lake Robbins Drive City: The Woodlands

State: TX Zip Code: 77380 Contact Phone: 832 636-3128

Lease: Green Court Farms Well #: A-1 Sec. 29 Twp. 28S R. 32 ☐ East ☒ West

S/2 S/2 NE NW Spot Location/QQQQ County Haskell

1250 Feet from (in exact footage) ☒ North / ☐ South (from nearest outside section corner) Line of Section (not Lease Line)

1980 Feet from (in exact footage) ☐ East / ☒ West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: ☒ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well
☐ SWD Docket # ☐ ENHR Docket # ☐ Other

Conductor Casing Size: Set at: Cemented with: Sacks

Surface Casing Size: 8-5/8" Set at: 1792' Cemented with: 875 Sacks

Production Casing Size: 5-1/2" Set at: 5338 Cemented with: 460 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4163'-5216'

Elevation: 2927 (☒ G.L. ☐ K.B.) T.D. 5757' PBTD 5264' Anhydrite Depth
(Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Bullhead in with 130 bbls of 9.0 mud. Mix
hulls with first 20 bbls. Set CTBP at 4120', dump 2 sxs of cement on CTBP. Set cement plugs from
1740'-1850', 450'-600', 4'-50' with 9.0 pop mud between each plug. Cut off and cap 8-5/8" casing @ 4'.

Is Well Log attached to this application as required? ☐ Yes ☒ No Is ACO-1 filed? ☐ Yes ☒ No

If not explain why?
RECEIVED
KANSAS CORPORATION COMMISSION
MAY 19 2004

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Conservation Commission
WICHITA, KS

List Name of Company Representative authorized to be in charge of plugging operations:

David Releford Phone: 620 482-1012

Address: 1707 W. 2nd Street City/State Liberal, KS 67901

Plugging Contractor Sargent & Horton Plugging, Inc. KCC License # 31151
(Company Name) (Contractor's)

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: 405 854-6515

Proposed Date and Hour of Plugging (if known?):

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-18-04 Authorized Operator / Agent: Jerry N. Blossom
(Signature)

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

May 26, 2004

Re: Green Court Farms #A1
API 15-081-20547-00-01
N2NW 29-28S-32W, 4030 FSL 3300 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely


David P. Williams
Production Supervisor