

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

Rev. 6-3-74
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
File One Copy

JUL 17 1975
7-17-75
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 137 - 20099 - 00 - 00 (of this well)
Lease Owner John P. Jennings
Address Suite 309, 200 East First Street, Wichita, Kansas 67202
Lease (Farm Name) HORESKY Well No. #1
Well Location NE NE SE Sec. 29 Twp. 3S Rge. (E) 23 (W) _____
County Norton Total Depth 3827' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin July 10, 1975 4:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Joe Weber Address Ellis, Kansas 67637

Plugging Contractor Abercombie Drilling, Inc. License No. #746

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name John P. Jennings

Address Suite 309, 200 East First Street, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed:

Jerry A. Langrehr
Applicant or Acting Agent

Jerry A. Langrehr

Date:

July 16, 1975

15-137-20099-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	John P. Jennings
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	HORESKEY #1
LOCATION:	NE NE SE Section 29-3S-23W Norton County, Kansas
GEOLOGIST:	Don D. Strong
SPUD DATE:	July 4, 1975
COMPLETION DATE:	July 10, 1975

0	150	Rock-Sand
150	175	Sand
175	200	Shale
200	206	Flint
206	1620	Shale
1620	1770	Sand
1770	2019	Shale
2019	2053	Anhydrite
2053	2360	Shale
2360	3500	Lime & Shale
3500	3827	Lime
	3827	Rotary Total Depth

Drilled 206' of 12 1/4" surface hole. Set 8 5/8" casing @206'. Cemented with 160 sx. Sunset cement. Cement circulated. Plug was down @5:30 p.m. July 4, 1975.
 Preparing to Plug: 1st Plug Set @1200' with 70 sx. cement; 2nd Plug Set @ 200' with 20 sx. cement; 3rd Plug Set @ 40' with 10 sx. cement. Cement: 50/50 Posmix w/6% gel. Plug was down @4:00 a.m., July 10, 1975. State Plugger: Gilbert Balthazor.

<u>Sample Tops:</u>		<u>Elevation:</u>
Anhydrite	2019	2413' K.B.
B/Anhydrite	2053	2411' D.F.
		2405' G.L.

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1975

CONSERVATION DIVISION
Wichita, Kansas

7-17-75

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HORESKEY #1, NE NE SE Section 29-3S-23W, Norton County, Kansas.


ABERCROMBIE DRILLING, INC

By: Jerry A. Langrehr
 Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of July 1975.

Nancy E. Haner
 Nancy E. Haner-Notary Public

My Commission Expires: April 8, 1978



State of Kansas



15-137-20099-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

July 22, 1975

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Horesky
Description	NE NE SE 29-3-23W
County	Norton
Total Depth	3827'
Plugging Contractor	Abercrombie Drilling, Inc.


John P. Jennings
Suite 309, 200 E. 1st
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, Route 1, Palco, Kansas
is hereby assigned to supervise the plugging of the above
named well.