



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Craig of Abercrombie Oil Co. (Big 10) has this date requested permission to plug the following described well:

Operator's Full Name: Duport Oil Company

Complete Address: 660 Edgewater Rd. - Wichita, Kans.

Lease Name: Hardman Well No. #1

Location: SW-NW-NW Sec. 36 Twp. 3 Rge. 19 (E) (W)

County: Phillips Total Depth: 3510 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Craig was instructed to plug the well as follows:

- 8 7/8" 324 FE 50. cu. w/ 225 st Commox - 2% Gel - 3% Ca Cl.
- Order 110 st 50 Premix 6% Gel. & 8 7/8" Plug.
- Spot with Drill Stem - with heavy mud between all Plugs.
- 1 st Plug @ 860 FE w/ 65 st Cmt.
- 2 nd Plug @ 330 FE w/ 30 st Cmt.
- 3 rd Plug - Solid Bridge @ 40 FE to 10 st Cmt.
- 5 st In Pat Hole

Very truly yours, (By) [Signature]

[Signature]
Conservation Division Agent

MAR 27 1981 3-27-81