



15-137-30086-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 - 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
12-1-70

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Csg. Pulling Co., Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: R. P. <sup>NIXON</sup> ~~Nixson~~ Operations, Incorporated,

Complete Address: 754 East Wichita Avenue, Russell, Kansas.

Lease Name: Horesky Well No. 1

Location: NW-SW-NE Sec. 29 Twp. 3 Rge. (E)(W) 23

County: Norton Total Depth 3816' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3812'--5 1/2" Production casing cemented on bottom with 100 Sx. Well  
plugged back to 3700'. Top perforations @ 3677'.

Sand back to 3650' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing  
and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement,  
staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent