



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 13 1964

CONSERVATION DIVISION
 Wichita, Kansas

7-13-64

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ed. Weiler of Shields Drilling Co. Inc., has this

date requested permission to plug the following described well:

R. P. Nixon *NIXON*
 Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: R. P. Nixon, *NIXON*

Complete Address: 754 E. Wichita, Russell, Kansas.

Lease Name: Horesky Well No. 1

Location: NWSE ~~SW-NW-NE~~ Sec. 29 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3780 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

200' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	185' with 1/4 sk. hulls & 20 Sx. cement.
"	"	40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

M. A. Nichols

Conservation Division Agent