



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 FEB 19 1963
 2-19-63
 CONSERVATION DIVISION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ray Richardson of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Cope Well No. 6

Location: W $\frac{1}{2}$ -W $\frac{1}{2}$ -NW Sec. 29 Twp. 3 Rge. (E) (W) 23

County Norton Total Depth 3751 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Richardson was instructed to plug the well as follows:

Sand well back to 3730', set 4 Sx cement w/Dump bailer.

Pull 5 $\frac{1}{2}$ " casing to 550', circulate heavy gel mud and displace

20 Sx cement thru 5 $\frac{1}{2}$ ". Pull 5 $\frac{1}{2}$ " to 240' and displace 20 Sx

cement thru 5 $\frac{1}{2}$ ". Pull 5 $\frac{1}{2}$ " casing set bridge @ 35' and 10 Sx

cement to bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent