



15-137-20079-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas

1-21-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Herschiser Well No. 1

Location: SW-SW-SE Sec. 34 Twp. 3 Rge. (E)(W) 23

County: Norton Total Depth 3800' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

33 1/4'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Cu. Ft. cement thru DP. Pull DP to 330' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*K. L. Nichols*  
Conservation Division Agent