

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 053-01803-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 1/1/51.

Well Operator: American Warrior Inc. KCC License #: 4058
(Owner / Company Name) (Operator's)
Address: P.O. Box 399 City: Garden City
State: Kansas Zip Code: 67846 Contact Phone: (620) 272 - 1023
Lease: Kraft-Prusa Well #: 9-1 Sec. 18 Twp. 17 S. R. 10 ☐ East ☒ West
C - NW - NW - NW Spot Location / QQQQ County: Ellsworth

4950' Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)
4950' Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☒ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well
☐ SWD Docket # _____ ☐ ENHR Docket # _____ ☐ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 85/8 Set at: 314' Cemented with: 150sx. Sacks
Production Casing Size: 51/2 Set at: 3248' Cemented with: 85sx. Sacks
List (ALL) Perforations and Bridgeplug Sets: 3153' to 3156'

Elevation: 1869" (☒ G.L. / ☐ K.B.) T.D.: 3263' PBTD: 3246' Anhydrite Depth: 640' to 665'
(Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill 51/2 casing to 3100' with sand and 2sx cement, pressure test 51/2 casing. Perf 1350' squeeze with 35sx common cement w/ 3% cc. Perf 900', Squeeze with 35sx common cement w/3%cc. Perf 365' Cir cement to surface.
Steve VanGieson

Is Well Log attached to this application as required? ☐ Yes ☒ No Is ACO-1 filed? ☒ Yes ☐ No

If not explain why? No logs on file.

RECEIVED
AUG 10 2004

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jody Smith

Phone: (620) 272 - 1023

Address: P.O. Box 399 City / State: Garden City Ks. 67846

Plugging Contractor: Swift Services, Inc. KCC License #: 32382
(Company Name) (Contractor's)

Address: P.O. Box 466 Ness City Ks. 67560 Phone: (785) 798 - 2300

Proposed Date and Hour of Plugging (if known?): NA

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/9/04 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

American Warrior, Inc.
PO Box 399
Garden City, KS 67846

August 10, 2004

Re: KRAFT-PRUSA #9-1
API 15-053-01803-00-00
NWNWNW 18-17S-10W, 4950 FSL 4950 FEL
ELLSWORTH COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely


David P. Williams
Production Supervisor