

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20926-00-01
Spot: S2NWNW Sec/Twnshp/Rge: 36-33S-11W
990 feet from N Section Line, 660 feet from W Section Line
Lease Name: POWELL Well #: 1-36 OWWO
County: BARBER Total Vertical Depth: 4750 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

CIBP Size: feet: 4600 WITH 2 SX CMT
PROD Size: 4.5 feet: 4750 WITH 185 SX CMT
SURF Size: 8.625 feet: 308

#154³⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/22/2004 1:15 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4600' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2004 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4716'. SET CIBP @ 4600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & RUN 2 3/8" TUBING IN TO PLUG THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4612	4630		

RECEIVED
AUG 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 8.5.04
INV. NO. 2005060311

Form CP-28 *[Signature]*